



# **Van Guard**

## **Sled Test Report**

Roof Rack Frame (Maxrack)  
Ladder Clamps  
Pipe Carrier

**A257I03**

**Copyright TRL March 11. All rights reserved.**

This is an unpublished report prepared for the customer named above and must not be referred to in any publication without the permission of the customer. The views expressed are those of the author(s) and not necessarily those of the customer

Test Engineers	C Walker / A Thompson
Quality review	S Ahmed

TRL Limited, Registered in England, Number 3142272  
Registered Offices: Crowthorne House, Nine Mile Ride, Wokingham, Berkshire, RG40 3GA, United Kingdom.  
A member of the Transport Research Foundation Group of Companies.

# Van Guard Sled Test

## Contents

Summary.....	3
A257I03.....	4
Test Details.....	4
Test Setup .....	4
Deceleration Pulse.....	4
Test Observations.....	5

## SUMMARY

Impact sled tests were performed on Van Guard roof accessories at TRL's Impact Sled Facility (ISF) on the 17<sup>th</sup> February 2011. The tests were undertaken according to the frontal impact deceleration pulse stipulated in ECE Regulation 17.

Customer	Van Guard
Test Facility	Impact Sled Facility
Test Numbers	A257I01
Test Date	17/02/2011
TRL Test Engineers	Chris Walker / Alex Thompson
Report Author	Alex Thompson

# A257I03

## Test Details

Test Procedure	ECE Regulation 17 frontal impact deceleration pulse
Test Description	Roof rack with attached pipe tube and ladder
Impact Speed	49.14 km/h
Peak Deceleration	23.78 g

## Test Setup


A set of van roof accessories were attached to the sled by Van Guard. These consisted of the following:

- Roof rack frame with associated brackets, attached to the sled at 4 mounting positions on either side
- One pipe tube containing 60 copper pipes attached to the roof rack frame in two places
- One ladder attached to the roof rack frame using two ladder clamps



## Deceleration Pulse

The deceleration pulse for the test was within the corridors specified in ECE Regulation 17.



## Test Observations

The following observations were made during the test:

- The roof rack frame withstood the impact and showed no obvious signs of deformation.
- The ladder displaced forward slightly during the impact but was restrained on the roof bars by the ladder clamps.
- The pipe tube withstood the impact and remained securely attached to the roof bars during the test. There was little forward displacement observed of the tube relative to the roof bars and no pipes came out of the tube during the impact.